KOLAR DIVISION.

Abstract.

The attention of the public is invited to the notification published on page 700 in the Gazette No. 45, dated 11th November 1920, calling for tenders for restoring Madalapalli tank, Reg. No. 725 of Chintamani Taluk.

Abstract.

The attention of the public is invited to the notification published on page 699 in the Gazette No. 45, dated 11th November 1920, calling for tenders for restoring Ammanallur tank, Reg. No. 266 of Kolar Taluk.

A. PUTTUSAMAIYA,
Executive Engineer.

SHIMOGA DISTRICT.

Dated 16th November 1920.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Benkipur Range, up to 12 noon, 20th December 1920, for constructing acqueduct, Relieving Weirs, Road and Cart Bridges on Bhadra Right Bank Channel. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1921.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Benkipur between the hours of 11 A.M. and 5 P.M. except on holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 for Section I, 300 for Section II, 400 for Section III in cash, or Government Promissory Notes, as earnest money, and be superscribed "Tender for construction of Masonry Works on Bhadra Right Bank Channel," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Tenders must comprise all works in any one section and not for any particular work in that section, but more than one section may be tendered for with a separate deposit for each.

Abstract Estimate of the probable cost of Constructing Acqueducts, Relieving weirs, Cart bridges, Foot bridges and Road bridges in the 1st 18 miles of Bhadra Right Bank Channel of Bhadra Anicut, Bhadrapuri, Shimoga District.

Number	Items of work	Per	I Section			II Section					III Section			
			Aqueduct at mile ½	Relieving weirs at miles 1 and 1½	Total	Cart bridges at miles ¼, ½, ¾, 1, 1¼ and 1½	Foot bridges at miles ¼ and ½	Relieving weirs at miles ¼, ½, ¾ and 1	Road bridges at mile ¼	Total	Cart bridges at miles ¼, ½, 1¼, 1½, 1¾, and 1⅞	Relieving weirs at miles ½, 1⅛, 1⅜, 1⅝ and 1⅞	Road bridges at miles ⅛ and ⅜	Total
1	Rough stone work	C. yd. ..	183	357	540	210	72	570	35	887	237	927	60	1,224
2	Blasting rock for foundation	C. yd. ..	469	..	469	..	..	..	..	..	..	..	..	..
3	Burnt stone in surki mortar	C. ft. ..	52,908	..	52,908	2,658	324	..	671	3,653	2,883	..	1,168	4,051
4	Burnt brick in surki mortar	Do ..	4,831	3,453	8,284	12,804	1,074	4,054	3,198	21,130	14,309	8,437	4,958	27,704
5	Plastering with surki mortar	Sqr. ..	32·00	20·11	52·11	90·68	4·00	28·18	24·47	147·33	100·63	49·47	35·34	185·44
6	Pointing with cement	Do ..	62·26	..	62·26	..	..	..	..	..	..	..	..	..
7	Burnt stone slabs 1′ thick	Sq. ft. ..	207	..	207	..	..	..	..	..	..	..	..	..
8	Do 9″ thick	Do ..	152	..	152	..	..	..	..	..	..	..	..	..
9	Do 6″ thick	Do ..	1,606	1,620	3,226	3,014	398	..	983	4,395	3,160	4,226	1,602	8,994
10	Do 3″ thick	Do ..	..	..	..	764	..	266	120	1,150	820	..	206	1,026
11	Cast iron standards and railings	R. ft. ..	164	..	164	..	..	..	..	..	..	..	..	..
12	Gravelling	C. yd. ..	10	..	10	82	..	..	31	113	86	..	54	140
13	Archwork brick in surki mortar	C. ft. ..	2,106	..	2,106	..	..	..	..	..	..	..	..	..
14	Concrete in surki mortar	Do ..	4,928	2,433	7,361	2,178	68	2,698	527	5,471	2,217	5,100	912	8,229
15	Clearing site, etc.	Per. ..	L. S.	L. S.	L. S.	..	..	..	..	..	..	..	..	..
16	Cornice work	R. ft. ..	66	..	66	632	..	..	96	728	656	..	160	816
17	Centerings for arches	Per. ..	L. S.	L. S.	L. S.	..	..	..	..	..	..	..	..	..
18	Earthwork excavation, and forming ramp gravelling, etc.	L. S. ..	L. S.	L. S.	L. S.	L. S.	L. S.	..	..	L. S.	..	..	..	..
19	Guard stones	No. ..	..	..	..	24	..	..	4	8	28	..	8	36
20	Earthwork excavation	C. yd. ..	..	408	408	L. S.	L. S.	446	L. S.	446	L. S.	984	L. S.	984
21	Rough stone in surki mortar	C. ft. ..	630	..	630	..	..	1,424	..	1,424	..	2,331	..	2,331
22	Stone blocks roughly dressed	Do ..	..	..	..	..	134	..	..	134	..	..	..	..

R. W. SCALDWELL,
Executive Engineer.

TUMKUR DIVISION.

Dated 10th November 1920.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 5 P.M. on 6th December 1920, for restoring Buradaghatta minor tank, Tiptur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1921.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M. on all days except Sundays and General holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rs. 100 only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Buradaghatta minor tank, Tiptur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer of Mysore who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned, on surrendering the Government receipts granted therefor.

Abstract estimate of quantities for restoring Buradaghatta minor tank, Regd. No. 156, of Tiptur Taluk.

Item No.	Items of work	Per	Quantity
	Bund.		
1	Earthwork, embanking, watering and tamping	C. yd.	2,458
2	Do breached portion	„	2,008
3	Constructing core wall at breach with burnt brick in surki mortar	C. ft.	468
4	Removing boulders and silt in breach for excavating foundation.	L. S.	...
5	Turfing	S. yd.	3,895
6	Providing grade with index stones, including cutting figures and painting	Each	24
7	Register No. ... stone	„	1
8	B. M. stone	„	1
9	Gauge stone	„	1
10	Resetting old stone revetment	C. yd.	342
11	New stone revetment	„	1,383
12	Removing jungle on bund and cutting grips for joining old and new earth	L. S.	...
	Constructing a waste weir in the right 60' long at R. S. 50·00.		
1	Burnt brick in surki mortar	C. ft.	360
2	Burnt stone slabs dressed	S. ft.	281
3	Plastering with surki mortar	Sqr.	1·17
4	Rough stone work, new	C. yd.	60
5	Earthwork excavating foundations, clearing drafts and approaches, etc.	L. S.	...

No.	Items of work	Per	Quantity
	Constructing a masonry sluice.		
1	Earthwork, cutting bund and refilling with consolidation ...	C. yd.	79
2	Burnt brick in surki mortar	C. ft.	507
3	Burnt stone slabs dressed	S. ft.	208
4	Plastering with surki mortar	Sqr.	5·23
	Removing and refixing old gibbet stones and boring holes to orifice slabs, etc.	L. S.	...
	Providing plug with teakwood rod	„	...

C. VIJAYARANGAM NAIDU,
Executive Engineer.

WATER-SUPPLY DIVISION.

Notice dated 13th November 1920.

Tenders for the supply of 110 of 15 inch internal diameter and 12 feet lengths cast iron spigot and socket turned and bored pipes will be received by the undersigned up to the 25th December 1920, as per specification noted below, which can be obtained from undersigned on application.

2. Each tender should be accompanied by a deposit of Rs. 1,500 in Government currency notes only as earnest money and should be sent in a sealed cover superscribed "Tenders for the supply of 15-inch diameter cast iron spigot and socket turned and bored pipes for the use of the Water-Supply Division.

3. The final acceptance of the tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

4. Within eight days of the accepted tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be cancelled and his earnest money, forfeited.

5. The name of the successful competitor, whose tender has been accepted will be posted on the 'notice board' in the undersigned's office in the usual course and no enquiries regarding the acceptance or rejection of a tender, will receive any reply.

6. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

7. Time of delivery of order in full to be noted in the tender.

Specification.

All the pipes except twelve which ought to be broad socket pipes, to be turned and bored of uniform bore and uniform thickness throughout without any belts and of the full specified diameters and to be perfectly free from sand, air holes, flaws and defects of any kind.

2. All pipes to be cast vertically with socket downwards in dry sand moulds.

3. The thickness and weight of the pipes to be as per standard trade practice, suitable for a working head of 500 feet, the least thickness being 7/8 inch.

4. The width and depth of sockets of the pipes to be made according to trade practice.

5. Each pipe to have its weight distinctly painted inside the socket after being dipped in Dr. Augus Smith's solution.

6. A margin in weight of not more than $2\frac{1}{2}$ per cent will be accepted.

7. The weight of the 15 inch diameter pipes to be of approximately $15\frac{1}{4}$ cwts.

8. All pipes to be made in strict accordance with the specification noted above.

G. V. RAO,
Executive Engineer.